CONSTRUCTION PLANS

UNION COUNTY BOAT RAMP

VICINITY MA

START ACCESS ROAD: STA. 10+00.00 END ACCESS ROAD: STA. 16+93.42 START BOAT RAMP: STA. 10+00.00 END BOAT RAMP: STA. 11+00.00

<u>UTILITIES</u>

TELEPHONE & CABLE
TRUVISTA
II2 YORK STREET
CHESTER, SC 2930I
JAMIE MILLIS, SR. PROJECT MANAGER
803-581-9130

AT&T TELEPHONE 100 BELTON DRIVE SPARTANBURG, SC 29301 MICHAEL NAT 864-573-4016

SPECTRUM
IIO COMMERCIAL ROAD
SPARTANBURG, SC 29303
DONNY PATTERSON
864-762-6038

ELECTRIC

LOCKHART POWER

420 RIVER ST., P.O. BOX 10


LOCKHART, SC 29364

JIM SEAY

864-545-2211

WATER & SEWER
TOWN OF LOCKHART WATER
P.O.BOX 250
LOCKHART, SC 29364
CARL ALEXANDER
864-545-2103

TOWN OF LOCKHART SEWER
P.O.BOX 250
LOCKHART, SC 29364
CARL ALEXANDER
864-545-2103



LAYOUT NTS

PREPARED FOR UNION COUNTY BY:



SHEET INDEX

1	TITLE SHEET
2	QUANTITY
3-3A	TYPICAL SECTION
4-4F	STANDARD DETAIL
4 G	SEDIMENT SHEET
5	UNION BOAT RAMP PLAN
6-7	PROFILE SHEETS

X1-X4 ACCESS ROAD CROSS SECTION SHEETS
X5 BOAT RAMP CROSS SECTION SHEETS
20 TOTAL

IHAVE PLACED MY SIGNATURE AND SEAL ON THE DESIGN
DOCUMENTS SUBMITTED SIGNIFYING THAT LACCEPT RESPONSIBILITY
FOR THE DESIGN OF THE SYSTEM. FURTHER, LCERTIFY TO THE
BEST OF MY KNOWLEDGE AND BELIEF THAT THE DESIGNS
CONSISTENT WITH THE REQUIREMENTS OF TITLE 48, CHAPTER 14
OF THE CODE OF LAWS OF SC, 1976 AS AMENDED, PURSUANT TO
REGULATION 72-300 ET SEQ. (IF APPLICABLE), AND IN
ACCORDANCE WITH THE TERMS AND CONDITIONS OF SCRIOOOOO.

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA

CALL I-888-72I-7877


Mead&Hunt


DRAWN BY: LMH
CHECKED BY:
SCALE: 30:1

SAROLINA

TITLE SHEET

UNION COUNTY





REVISION					


STATE COUNTY ROAD/ROUTE NO. SHEET
SC UNION BOAT RAMP 2

SUMMERY OF ESTIMATED QUANTITIES


BASE BID

ITEM	DESCRIPTION	QUANTITY	UNIT
1031000	MOBILIZATION	NEC.	LS
2011000	CLEARING & GRUBBING WITHIN RIGHT OF WAY	NEC.	LS
2031000	UNCLASSIFIED EXCAVATION	5,819	CY
2033000	BORROW EXCAVATION	5,042	CY
3050106	GRADED AGGREGATE BASE COURSE (8" UNIFORM)	3,526	SY
3065134	BALLAST STONE - NO. 4	336	TON
3100320	H/M ASPH. BASE CRTYPE B	24	TON
4011004	LIQUID ASPHALT BINDER PG64-22	20	TON
4020330	H/M ASPH.INTERMEDIATE CR.TYPE C	10	TON
4030340	2" H/M ASPHALT SURFACE COURSE TYPE C	335	TON
6271025	24" WHITE SOLID LINES (STOP/DIAG LINES)-THERMO125 MIL	17	LF
6271050	HANDICAP SYMBOL - THERMOPLASTIC - 125 MIL.	2	EA
6271074	4" YELLOW SOLID LINES(PVT.EDGE LINES) THERMO-90 MIL.	949	LF
6271080	24" YELLOW SOLID LINES -THERMO125 MIL	135	LF
6510105	FLAT SHEET, TYPE III, FIXED SIZE	17.25	SF
7011100	CONCRETE FOR STRUCTURES - CLASS 3000 (ROADWAY)	25	CY
7141112	15" RCP	48	LF
7141113	18" RCP	96	LF
7191205	CATCH BASIN - TYPE 9	1	EA
8041020	RIP-RAP (CLASS B)	193	TON
8048205	GEOTEX/EROS.CONT(CLASS2)TYPE B	520	SY
8100001	PERMANENT VEGETATION	2.913	**MSY
8103100	TEMPORARY VEGETATION	5.260	**MSY
8151101	TURF REINFORCEMENT MATTING (TRM) TYPE 1	1.937	**MSY
8151111	TEMP. EROSION CONTROL BLANKET	1.550	**MSY
8152004	INLET STRUCT.FILTT-F(WEIGHT)	48	LF
8152006	INLET STR.FILTT-F(NON-WEIGHT)	48	LF
8153000	NPDES SILT FENCE	1,025	LF
8156490	STABILIZED CONSTRUCTION ENTRANCE	310	SY
CONTINGE	NT ITEMS		
ITEM	DESCRIPTION	QUANTITY	UNIT
1071000	TRAFFIC CONTROL	NEC.	LS
2033000	BORROW EXCAVATION	575	CY
2034000	MUCK EXCAVATION	750	CY
3069900	MAINTENANCE STONE	145	TON
8156300	SEDIMENT DAM RIPRAP	50	TONS
8156490	STABILIZED CONSTRUCTION ENTRANCE	310	SY






STATE COUNTY ROAD/ROUTE NO. SHEET NO.
SC UNION BOAT RAMP 3A




TYPICAL 4



TYPICAL MINIMUM PAVEMENT SECTION NOT TO SCALE

*COMPACTED THICKNESS.




Mead&Hun

UNION COUNTY, SOUTH CAROLINA

CHECKE

TYPICAL SECTION SHEET





EROSION CONTROL NOTES

- IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
- WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE - WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED. AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED. THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION
- PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES. AS MAY BE REQUIRED. TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING. THE WATER SHOULD BE FILTERED TO REMOVE SEDIMENT BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- 6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
- TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
- LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 10. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 11. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS.

12.MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS(SEDIMENT BASIN. FILTER BAG, ETC.)

- 13. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
- -WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL: -WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS:
- -FUELS. OILS. OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND
- SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 14. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 15. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF SC'S WATER QUALITY STANDARDS. IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- 16. ALL TIMBERING TO BE PREFORMED USING LOW GROUND PRESSURE, TRACKED EQUIPMENT.
- STRUCTURAL FILL LIFTS TO BE DONE IN EIGHT INCHES OR LESS.

GENERAL CONSTRUCTION NOTES

- 1. ALL WORK ON THIS PROJECT SHALL BE DONE IN ACCORDANCE WITH THE SPECIAL PROVISIONS, THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2007 EDITION), AND THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD DRAWINGS. ALL REFERENCES TO THE SPECIFICATIONS ON THE PLANS SHALL REFER TO THE SPECIAL PROVISIONS, UNLESS OTHERWISE NOTED.
- 2. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO HAVE THE LATEST SET OF THESE PLANS AND SPECIAL PROVISIONS AND ANY REFERENCED SCDOT STANDARDS AT THE TIME OF NOTICE TO PROCEED.
- 3. BOUNDARY AND TOPOGRAPHIC INFORMATION FURNISHED BY BIDDING CONTRACTOR
- 4. HORIZONTAL CONTROL: IT IS THE CONTRACTORS RESPONSIBILITY TO ESTABLISH THE COORDINATES FOR THIS PROJECT ON SOUTH CAROLINA STATE PLANE NAD 83 (2007).
- 5. VERTICAL CONTROL: THE LOCATION AND ELEVATION OF BENCHMARKS ARE THE RESPONSIBILITY OF THE CONTRACTOR. ALL ELEVATIONS SHOWN ARE IN FEET BASED ON NAVD 88 DATUM.
- 6. ALL PROJECT INSPECTION LOGS / CERTIFIED TEST RESULTS SHALL BE SUBMITTED TO THE OWNER WITH EACH PAY REQUEST.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CUTTING AND MAINTAINING THE PERMANENT AND/OR TEMPORARY STABILIZATION ALONG THE PROJECT LIMITS IN ACCORDANCE TO THE SCDOT SPECIFICATIONS. THIS WORK IS INCIDENTAL TO THE TOTAL COST OF THE PROJECT AND SHALL BE CONTRACTORS RESPONSIBILITY UNTIL THE START OF THE WARRANTY PERIOD
- 8. ALL INVERT ELEVATIONS ARE APPROXIMATE. INVERT ELEVATIONS OF INLETS AND PIPES MAY BE MODIFIED AS DIRECTED BY THE ENGINEER TO MEET THE CONDITIONS ENCOUNTERED DURING INSTALLATION OF DRAINAGE STRUCTURES. ALL DITCHES AND PIPES SHALL BE CONSTRUCTED ON UNIFORM GRADE BETWEEN INVERT ELEVATIONS, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 9. THE LOCATION AND LENGTH OF PIPE SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO ORDERING. 10. THE CONTRACTOR SHALL REMOVE ALL SEDIMENT AND DEBRIS FROM ALL PIPES WITHIN THE PROJECT LIMITS UPON COMPLETION
- OF THE WORK. 11. THE CONTRACTOR SHALL GRADE FOR POSITIVE DRAINAGE AT ALL ROADWAY INTERSECTIONS, ENTRANCES, PARKING LOTS, AND
- YARDS IN CONFORMANCE WITH THE PROPOSED DRAINAGE PATTERNS ON THE PLANS.
- 12. UTILITIES:
- A. THE LOCATIONS OF UNDERGROUND AND AERIAL UTILITIES <u>ARE NOT</u>SHOWN ON THE PLANS AND ARE TO BE FIELD VERIFIED PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY PUPS TO ARRANGE STAKEOUT OF UTILITIES AT LEAST 3 DAYS PRIOR TO STARTING CONSTRUCTION. THE CONTRACTOR MUST PROTECT, IN PLACE, ALL ACTIVE UNDERGROUND UTILITIES UNLESS OTHERWISE NOTED . NO S.U.E. OR VERTICAL LOCATIONS HAVE BEEN COMPLETED AS PART OF THE PROJECT.
- B. REPAIRS TO UTILITIES OR PROPERTY DAMAGE AS A RESULT OF CONTRACTOR NEGLIGENCE OR METHOD OF OPERATION SHALL BE MADE AT NO ADDITIONAL COST TO THE COUNTY OR PROPERTY OWNER.
- C. THE CONTRACTOR SHALL PROTECT AND NOT INTERRUPT EXISTING UTILITY SERVICES DURING CONSTRUCTION, UNLESS AUTHORIZED BY THE ENGINEER. THE CONTRACTOR SHALL SUPPORT EXISTING UNDERGROUND UTILITIES DURING CONSTRUCTION. THIS WORK SHALL BE INCIDENTAL TO THE PERTINENT PAY ITEMS. PORTIONS OF THE UTILITIES MAY BE RELOCATED IF APPROVED BY UTILITY SERVICE PROVIDER PRIOR TO RELOCATIONS.
- D. ALL UNDERGROUND UTILITIES AND/OR CONDUITS AT PAVED AREAS MUST BE IN PLACE PRIOR TO THE PAVEMENT BASE CONSTRUCTION. CONTRACTOR SHALL ENSURE COMPACTION IN ALL UTILITY LOCATIONS.
- E. THE CONTRACTOR SHALL ADJUST TO GRADE ALL EXISTING MANHOLES, VALVE BOXES, OR OTHER UTILITIES LOCATED WITHIN THE OVERLAY AREA. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT AND NECESSARY TO COMPLETE THE WORK, UNLESS OTHERWISE STATED.
- 13. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE MAINTENANCE OF TRAFFIC THROUGHOUT THE ENTIRE PERIOD OF CONSTRUCTION BY PROVIDING A REASONABLY SMOOTH AND EVEN SURFACE SATISFACTORY FOR THE USE OF PUBLIC TRAFFIC AND TO PROVIDE ACCESS TO ALL PUBLIC ROADS AND RESIDENTIAL ENTRANCES AT ALL TIMES.
- 14. ALL EXISTING ROADWAY SIGNAGE SHALL BE RELOCATED, REUSED OR REPLACED AS INDICATED BY THE ENGINEER, OR AS DEEMED NECESSARY TO PERFORM THE WORK. IF THE ROADWAY REMAINS OPEN TO TRAFFIC DURING CONSTRUCTION, ALL SIGNS THAT ARE TO BE RELOCATED SHALL BE ERECTED IN A TEMPORARY MANNER THAT DOES NOT IMPEDE TRAFFIC FLOW. ANY SIGN MESSAGE THAT CONFLICTS WITH THE CONSTRUCTION TRAFFIC CONTROL SIGNAGE SHALL BE COVERED OR TEMPORARILY REMOVED.
- 15. CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE ACCESS FOR MAIL SERVICE DURING CONSTRUCTION. IF NECESSARY, CONTRACTOR SHALL COORDINATE ANY TEMPORARY MAILBOX RELOCATIONS WITH UNITED STATES POSTAL SERVICE.
- 16. THE CONTRACTOR SHALL ADHERE TO THE WEIGHT LIMITS PRESCRIBED ON SCDOT/COUNTY MAINTAINED ROADS FOR HAULING EQUIPMENT AND/OR MATERIALS TO AND FROM THIS SITE. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY DAMAGES TO THE ROADS AND/OR UTILITIES DUE TO NONCOMPLIANCE OF WEIGHT LIMIT REGULATIONS.
- 17. THE CONTRACTOR SHALL MAKE, CHECK, AND BE RESPONSIBLE FOR ALL MEASUREMENTS AND DIMENSIONS NECESSARY FOR THE PROPER CONSTRUCTION OF ALL WORK. ALL ROAD WIDTH LAYOUT DIMENSIONS SHOWN ARE TO THE EDGE OF TRAVELWAY.
- 18. ALL RESIDENTIAL DRIVEWAYS SHALL BE RECONSTRUCTED AS DIRECTED BY THE ENGINEER. ANY CHANGES TO INDIVIDUAL DRIVEWAYS SHALL BE COORDINATED WITH THE ENGINEER.
- 19. ALL DRIVEWAY CULVERTS SHALL BE RCP PIPE.
- 20. THE CONTRACTOR MUST NOT OCCUPY ANY NON-PERMITTED WETLAND AREAS.
- 21. THE COUNTY ENGINEER MUST SPECIFICALLY AUTHORIZE CHANGES INVOLVING INCREASED COST OF THE PROJECT. THE COUNTY'S REPRESENTATIVE IS PERMITTED UNDER THE DIRECTION OF THE COUNTY ENGINEER TO AUTHORIZE MINOR ALTERATIONS NOT IN CONFLICT WITH THE STANDARD PRACTICES OF THE COUNTY AND/OR SCDOT.
- 22. THE CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING THE HORIZONTAL AND VERTICAL ALIGNMENT CONTROLS FOR THE PROJECT. THE CONTRACTOR IS TO ADJUST ALIGNMENT AS NECESSARY IN ORDER TO AVOID EXISTING FENCES, STRUCTURES, GATES, ETC. THE CONTRACTOR MUST NOTIFY THE RCE OF ANY MODIFICATIONS TO THE ALIGNMENT PRIOR TO ADJUSTMENTS.
- 23. THE CONTRACTOR SHALL CONDUCT A SITE VISIT WITH RCE. THE CONTRACTOR SHALL STAKE OUT ALL OUTFALL LOCATIONS AND PIPE LOCATIONS PRIOR TO THE SITE VISIT. THE CONTRACTOR MUST ALSO STAKE OUT THE LOCATIONS WHERE THERE WILL BE A CHANGE IN THE TYPICAL SECTION. THE CONTRACTOR IS REQUIRED TO OBTAIN WRITTEN APPROVAL OF THESE LOCATIONS PRIOR TO BEGINNING CONSTRUCTION.
- 24. THE CONTRACTOR IS TO REPAIR THE SUBGRADE AFTER CLEARING AND GRUBBING AT THE DIRECTION OF THE ENGINEER.
- 25. THE CONTRACTOR IS TO REFRAIN FROM THE USE OF COFFER DAMS AS WELL AS ANY DEWATERING CONSTRUCTION METHODS OR ACTIVITIES DURING THE CONSTRUCTION OF THE BOAT RAMP, PARKING AREA, OR ACCESS ROAD. THE CONTRACTOR IS TO SUBMIT A PLAN TO CONSTRUCT THE BOAT RAMP TO THE ENGINEER FOR REVIEW 20 WORKING DAYS PRIOR TO BEGINNING CONSTRUCTION
- 26. PRIOR TO BEGINNING ANY LAND DISTURBING ACTIVITY, APPROPRIATE EROSION AND SILTATION CONTROL MEASURES (I.E. SILT FENCES OR BARRIERS) MUST BE IN PLACE AND MAINTAINED IN A FUNCTIONING CAPACITY UNTIL THE AREA IS PERMANENTLY STABILIZED.
- 27. MATERIALS USED FOR EROSION CONTROL (E.G. HAT BALES OR STRAW MULCH) WILL BE CERTIFIED AS WEED FREE BY THE
- 28. INSPECTORS OF TEMPORARY EROSION CONTROL MEASURES SHOULD BE CONDUCTED ON A DAILY BASIS IN AREAS OF ACTIVE CONSTRUCTION OR EQUIPMENT OPERATION.
- 29. ALL NECESSARY MEASURES MUST BE TAKEN TO PREVENT OIL, TAR, TRASH, AND OTHER POLLUTANTS FROM ENTERING THE
- 30. UPON PROJECT COMPLETION, ALL DISTURBED AREAS MUST BE PERMANENTLY STABILIZED WITH VEGETATIVE COVER (PREFERABLE) RIP RAP OR OTHER EROSION CONTROL METHODS AS APPROPRIATE.
- 31. CONSTRUCTION ACTIVITIES MUST AVOID AND MINIMIZE, TO THE GREATEST EXTENT PRACTICABLE, DISTURBANCE OF WOODY SHORELINE VEGETATION OUTSIDE PROJECT AREA. REMOVAL OF VEGETATION SHOULD BE LIMITED TO ONLY WHAT IS NECESSARY FOR THE PROPOSED ACTIVITIES AND SHOULD BE CONDUCTED MANUALLY TO LEAVE LOW GROWING, WOODY VEGETATION AND SHRUBS IN THEIR PLACE IN RIPARIAN AREAS TO MAINTAIN STREAM BANK STABILITY AND REDUCE EROSION. DISTURBED STREAM BANKS CAN BE RESTORED BY PLANTING WOODY VEGETATION IN TEMPORARY CLEARINGS AND BY USING BIOENGINEERING TECHNIQUES IN PERMANENT CLEARING TO ENSURE STREAM BANK STABILIZATION.
- 32. IN-STREAM CONSTRUCTION ACTIVITIES SHOULD NOT OCCURRED DURING FISH SPAWNING SEASON FROM MARCH 1ST TO JUNE 30TH DUE TO ITS NEGATIVE IMPACTS ON EGGS AND REPRODUCTION ACTIVITIES
- 33. FOLLOWING COMPLETION OF THE PROJECT, WHERE NECESSARY, TEMPORARY REMOVAL OF VEGETATION OCCURRED, SUPPLEMENTAL PLANTING SHOULD BE INSTALLED. THESE PLANTINGS SHOULD CONSIST OF APPROPRIATE NATIVE, SPECIES FOR THE ECOREGION.

ROAD/ROUTE NO. SHEET NO. UNION BOAT RAMP

SURVEY DATA

(•) – IPF/IRF – IRON PIN/REBAR FOUND

- ROADSIGN

■O■ – FHY – FIRE HYDRANT

SYMBOL LEGEND:

- MAII MB - MAII BOX/PAPER BOX

- TELPED - TELEPHONE PEDESTAL

PP – POWER POLE

– GUY WIRE

----- - LIMITS OF CONSTRUCTION - ROCK CHECK DAM

—× – FENCELINE – SHRUB

WATER METER GAS VALVE


- WITNESS MARKER *WATERVALVE*


- SEWER CLEANOUT

– CABLE TV BOX

= = - EXISTING PIPES - PROPOSED DRAINAGE PIPES

ALL DRIVEWAY RADII WILL BE 5' MINIMUM AND ALL DRIVEWAY WIDTHS WILL BE 15' MINIMUM UNLESS OTHERWISE NOTED ON PLANS.





CRUSHED STONE

SLOPE TRENCH

AS PER OSHA -REQUIREMENTS

- 1. BEDDING IS REQUIRED WHEN TRENCH BOTTOM IS BELOW THE WATER TABLE.
- 2. BEDDING SHALL BE COMPACTED CRUSHED STONE (CLASS 1 MATERIAL)
- 3. FILL SHALL BE SUITABLE MATERIAL IN NON PAVEMENT AREAS AND AGGREGATE BACKFILL MATERIAL IN PAVEMENT AREAS AND COMPACTED TO 95% OF THE SOILS
- 4. FILL SHALL BE NATIVE MATERIAL FREE OF LARGE ROCKS, DEBRIS OR ORGANICS AND COMPACTED TO 95% OF THE SOIL'S STANDARD PROCTOR.
- 5. FILTER FABRIC TO BE PLACED AT ALL JOINTS.


REINFORCED CONCRETE PIPE BEDDING DETAIL SCALE: N.T.S.

O


CAROLINA

UNION

TH CARO HUNT, INC. No. C04334




RAMP GROOVING DETAIL SCALE: N.T.S.



TYPICAL V-GROOVE FINISHING TOOL

SECTION B-B

USE 1" x 1" x 3/16" ALUM. ANGLE



CONCRETE RAMP SHALL BE BULL FLOATED AND COMPACTED TO A UNIFORM LEVEL BEFORE GROOVING PROCEDURE TAKES PLACE

TYPICAL "V" GROOVE SCALE: N.T.S.

RAMP GROOVING NOTES:

THE GROOVING TOOL SHALL BE PUSHED OR PULLED ACROSS THE SURFACE OF THE CONCRETE IN A REASONABLY STRAIGHT LINE IN ONE CONTINUOS PASS FROM OR TO THE CENTERLINE AT THE SPECIFIED ANGLE. THE TOOL SHALL PENETRATE THE SURFACE OF THE CONCRETE NO LESS THAN 3/4". CAUTION SHALL BE TAKEN IN PERFORMING THE V- GROOVE FINISH AT THE PROPER TIME SO THAT THE GROOVES SHALL BE RELATIVELY SMOOTH AND UNIFORM, WITHOUT UNNECESSARILY TEARING THE SURFACE OF THE CONCRETE. THE FINISHED SURFACE SHALL BE PROTECTED FROM RAINFALL AND RUNOFF, AND FREEZING WEATHER.

RAMP CONSTRUCTION NOTES

1) ALL EXCAVATED MATERIALS SHALL BE UTILIZED AS FILL MATERIAL. ANY UNSUITABLE MATERIAL SHALL BE REMOVED FROM THE SITE AND DISPOSED OF ON PROPER HIGH GROUNDS.

2) DIRT SUB-GRADES SHALL BE COMPACTED PRIOR TO PLACING ANY DIRT OR ROCK FILL MATERIAL. ALL ROCK FILL, INCLUDING RAILROAD BALLAST, SHALL BE COMPACTED PRIOR TO PLACING CONCRETE.

3) ALL CONCRETE USED IN CONSTRUCTION OF RAMP SHALL BE A MINIMUM OF 3000 PSI MIX DESIGN. CONCRETE SHALL BE SPRAYED WITH AN APPROVED CURING COMPOUND

4) ALL CONCRETE POURED SHALL BE COVERED WITH PLASTIC AFTER FINISHING AND INITIAL SETTING HAS OCCURRED. IT SHALL REMAIN COVERED FOR NO LESS THAN (7) DAYS THEREAFTER.

5) WHEN PLACING CONCRETE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR TAMPING FORM BOARDS TO ELIMINATE HONEY COMBS OR AIR BUBBLES ON ALL FORMED SURFACES. HE WILL BE REQUIRED TO RUB SURFACES WITH A GROUT MIX IF FINISH IS UNSATISFACTORY.

6) USE ONLY CONCRETE RAKES OR COME-ALONGS WHEN PLACING CONCRETE. (NO GARDEN RAKES)

7) IT IS RECOMMENDED THAT THE CONCRETE BE POURED IN THE MORNING HOURS OF THE DAY TO HELP PROTECT THE FINISHED SURFACE FROM ANY DAMAGE (I.E.-FOOTPRINTS, GRAFFITI, ETC.) TO THE SURFACE OF THE CONCRETE.

8) ALL GRADES AND REFERENCE LINES ARE TO BE SET BY THE CONTRACTOR AFTER INITIAL TAKE OFF POINTS ARE SET. BENCHMARKS AND ELEVATION REFERENCES SET BY SCDNR.


9) SILT FENCES SHALL BE IN PLACE PRIOR TO GRADING. IF ANY EXCAVATED MATERIALS THAT ARE TO BE STOCK PILED ON SITE, SILT FENCING (OR) HAY BALES SHALL BE PLACED AROUND THESE PILES TO PREVENT ANY SILT LADEN WATERS FROM ENTERING THE ADJACENT WATER BODY OR LANDS.

10) SEED ALL DISTURBED AREAS WITH A PERMANENT TYPE VEGETATION TO PREVENT EROSION. VEGETATION SHALL BE ESTABLISHED PRIOR TO THE COMPLETION OF PROJECT AND BEFORE SILT FENCES ARE REMOVED.

11) RIP-RAP SHALL BE CLEAN AND FREE OF OIL AND DEBRIS. IT SHALL BE ONE-MAN SIZED AND PLACED A MINIMUM ONE FOOT THICK OVER FILTER FABRIC. NO FABRIC SHALL BE SHOWING THROUGH THE RIP-RAP STABILIZATION.

12) CONTRACTOR SHALL TAKE THE NECESSARY PRECAUTIONS TO PROTECT THE TREES FROM DAMAGE ADJACENT TO THE PROJECT AREA.

13) ALL WORK SHALL COMPLY WITH THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION." SEE PAVING NOTES ON SHEET 2 OF 2



CONTRACTOR TO WORK WITH COUNTY TO MATCH SIGN AS SHOW IN DETAIL.

ITEM TO BE PAID BY 6510106 - FLAT SHEET, TYPE III, SIZE DETERMINED BY MESSAGE - 8 SF

CHAIN DATA

STATE	COUNTY	ROAD/ROUTE NO.	SHEET NO.
SC	UNION	BOAT RAMP	4A

Beginning chain ALT1 description ______

N 1,078,774.6382 E 1,860,508.3950 Sta

Course from 1 to PC ALT11 N 35° 52' 27.80" E Dist 32.0393

Curve Data

Curve ALT11

10+58.16 N 1,078,821.7684 E 1,860,542.4795

= 47° 03′ 25.72″ (RT) Degree 95° 29′ 34.68″ Tangent 26.1243 Length 49.2781

60.0000 Radius 5.4407 External = Long Chord = 47.9048

Mid. Ord. = 4.9883 10+32.04 N 1.078.800.5998 E 1.860.527.1704 P.C. Station P.T. Station 10+81.32 N 1,078,824.9832 E 1,860,568.4053

N 1,078,765.4392 E 1,860,575.7886

Back = N 35° 52′ 27.80″ E Ahead = N 82° 55′ 53.52″ E Chord Bear = $N 59^{\circ} 24' 10.66'' E$

Course from PT ALT11 to PC ALT12 N 82° 55′ 53.52" E Dist 437.5795

Curve Data

Curve ALT12

15+53.72 N 1.078.883.1154 E 1.861.037.2219

40° 15′ 59.02″ (LT) Degree 60° 18′ 40.85″ Tangent 34.8275 Length 66.7642 95.0000 External = 6.1828 Long Chord =

Mid. Ord. = 5.8050 P.C. Station 15+18.90 N 1,078,878.8296 E 1,861,002.6591 15+85.66 N 1,078,908.7249 E 1,861,060.8249 N 1,078,973.1076 E 1,860,990.9688

Back = $N 82^{\circ} 55' 53.52'' E$ Ahead = $N 42^{\circ} 39' 54.50'' E$ Chord Bear = N 62° 47' 54.01" E

Course from PT ALT12 to 2 N 42° 39' 54.50" E Dist 112.2014

N 1,078,991.2297 E 1,861,136.8652 Sta 16+97.86

Ending chain ALT1 description

Beginning chain ALT1 RAMP-NEW description

N 1,079,016.4734 E 1,861,102.9248 Sta 10+00.00

Course from 212 to 213 N 42° 39' 54.50" E Dist 100.0000

N 1,079,090.0061 E 1,861,170.6961 Sta 11+00.00 Point 213

______ Ending chain ALT1 RAMP-NEW description

CAROLINA

DETAIL SOUTH STANDARD

UNION





SHEET

CONSTRUCTION SEQUENCE

ELEVATION POINT NORTHING EASTING DESCRIPTION 1078613 1860672 438.161 **CP-REBAR** 101 453.1326 102 1078780 1860446 **CP-REBAR** 103 1078768 1860757 447.2965 CP-NAIL 104 1078876 1860631 440.2241 CP-NAIL 1078899 1860747 105 430.5091 CP-NAIL 1078903 1860825 419.5991 106 CP-NAIL 107 1078958 1860914 405.6484 CP-NAIL 1861060 1079077 399.881 CP-NAIL 1861015 CP-NAIL 1079010 399.7301 1078735 1861007 463.3385 CP-NAIL

CONTROL POINTS

1.RECEIVE NPDES APPROVAL FROM SC DHEC 2.PRE-CONSTRUCTION MEETING 3.CLEARING & GRUBBING ONLY AS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS 4.INSTALL PERIMETER CONTROLS (E.G. SILT FENCE)

5.CLEARING & GRUBBING OF SITE 6.ROUGH GRADING

7.INSTALL STORM DRAINAGE, OUTLET STRUCTURES, AND OUTFALL DITCHES 8.INSTALL TEMPORARY SEDIMENT & EROSION CONTROL ITEMS

9.FINE GRADING & STONE APPLICATION

10.PERMANENT STABILIZATION 11.REMOVE TEMPORARY SEDIMENT & EROSION CONTROL MEASURES AFTER ENTIRE AREA DRAINING TO

STRUCTURE MEETS FINAL STABILIZATION REQUIREMENTS 12.SUBMIT THE NOTICE OF TERMINATION (NOT) TO SC DHEC

STANDARD NOTES

I. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.

2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW

- WHERE STABILIZATION BY THE 14" DAY IS PRECLUDED BY SNOW OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE - WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SIRE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO B INITIATED ON THAT PORTION OF THE SITE

3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK.IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BPM HAS BEEN INAPPROPRIATELY,OR INCORRECTLY,PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BPM WITHIN 48 HOURS OF IDENTIFICATION.

4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE SEDIMENT BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.

5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.

6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO THE PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.

8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS

9. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.

IO. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.

II. A COPY OF THE SWPPP, INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.

12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:IV OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.

13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.

14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE;

15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS.THESE DISCHARGE ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ECT.).

16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:

-WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE

CONTROL

- WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS;

- FUEL,OILS,OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND

- SOAPS OR SOLVENTS USED IN VEHICLES AND EQUIPMENT WASHING


17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVER CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.


18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATIONS MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.


19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.


STATE COUNTY ROAD/ROUTE NO. SHEET NO.


SC UNION BOAT RAMP 4B












STATE COUNTY ROAD/ROUTE NO. SHEET NO. SC UNION BOAT RAMP 4C

RIPRAP: INSPECTION AND MAINTENANCE

ONCE A RIPRAP INSTALLATION HAS BEEN COMPLETED , IT SHOULD REQUIRE VERY LITTLE MAINTENANCE

IT SHOULD, HOWEVER, BE INSPECTED PERIODICALLY TO DETERMINE IF HIGH FLOWS HAVE CAUSED SCOUR BENEATH THE RIPRAP AND FILTER FABRIC OR DISLODGED ANY OF THE STONE

CARE MUST BE TAKEN TO PROPERLY CONTROL SEDIMENT-LADEN CONSTRUCTION RUNOFF THAT MAY DRAIN TO THE POINT OF THE NEW INSTALLATION. IF REPAIRS ARE NEEDED, THEY SHOULD BE PREFORMED IMMEDIATELY



Tead & Flun


878 SOUTH LAKE DRIN LEXINGTON, SC 29072

DRAWN BY: LMH
CHECKED BY:
SCALE: 30:1


COUNTY, SOUTH CAROLINA STANDARD DETAIL

MEAD & HUNT, INC.
No. C04334

NOINO



REVISION



ROCK DITCH CHECK - GENERAL NOTES

 Rock Ditch Checks should not be placed in Waters of the State or USGS blue—line streams (unless approved by Federal Authorities).

- 2. Rock Ditch Checks should be installed in steeply sloped channels where adequate vegetation cannot be established. This BMP measure should only be used in small open channels.
- 3. A non-woven geotextile fabric shall be installed over the soil surface where the rock ditch check is to be placed.
- 4. The body of the rock ditch check shall be composed of 12—inch D50 Riprap. The upstream face may be composed of 1—inch D50 washed stone.
- Rock Ditch Checks should not exceed a height of 2—feet at the centerline of the channel.
- Rock Ditch Checks should have a minimum top flow length of 2—feet.
- Riprap should be placed over channel banks to prevent water from cutting around the ditch check.
- 8. The riprap should be placed by hand or mechanical placement (no dumping of rock to form dam) to achieve complete coverage of the channel. Doing so will also ensure that the center of the check is lower than the edges.
- 9. The maximum spacing between the dams should be such that the toe of the upstream check is at the same elevation as the top of the downstream check.

ROCK DITCH CHECK - INSPECTION & MAINTENANCE

- The key to functional rock ditch check is weekly inspections, routine maintenance, and regular sediment removal.
- Regular inspections of rock ditch checks shall be conducted once every calendar week and, as recommended, within 24-hours after each rainfall even that produces 1/2-inch or more of precipitation.
- 3. Attention to sediment accumulations in front of the rock ditch check is extremely important. Accumulated sediment should be continually monitored and removed when necessary.
- Remove accumulated sediment when it reaches 1/3 the height of the rock ditch check.
- Removed sediment shall be placed in stockpile storage areas or spread thinly across disturbed area. Stabilize the removed sediment after it is relocated.
- 6. Inspect Rock Ditch Checks' edges for erosion and evidence of runoff bypassing the installed check. If evident repair promptly as necessary to prevent erosion and bypassing.
- 7. In the case of grass—lined ditches, channels, and swales, rock ditch checks should be removed when the grass has matured sufficiently to protect the ditch or swale unless the slope of the swale is greater than 4%.
- 8. After construction is completed and final stabilization is reached, the entirety of the rock ditch check should be removed if vegetation will be used for permanent erosion control measures. The area beneath the removed rock ditch check must be addressed with permanent stabilization

South Carolina Department of Health and Environmental Control

ROCK DITCH CHECK

STANDARD DRAWING NO. SC-04 PAGE 2 of 2

GENERAL NOTES FEBRUARY 2014
DATE

STATE COUNTY ROAD/ROUTE NO. SHEET NO.

SC UNION BOAT RAMP 4D

Mea


'8 SOUTH LAKE DRIVE EXINGTON, SC 29072 ELEPHONE: (803)996-2900

DRAWN BY: LMH
CHECKED BY:
SCALE: 30:1

JTH CAROLINA


COUNTY, SOUTH CA

NON NEAD & HUNT, INC.



NOI					
REVISION					


COUNTY ROAD/ROUTE NO. SHEET NO. UNION BOAT RAMP



SILT FENCE — GENERAL NOTES

1. Do not place silt fence across channels or in other areas subject to concentrated flows. Silt fence should not be used as a velocity control BMP. Concentrated flows are any flows greater than 0.5 cfs.

- . Maximum sheet or overland flow path length to the silt fence shall be 100—feet.
- Maximum slope steepness (normal [perpendicular] to the fence line) shall be 2:1.
- 4. Silt fence joints, when necessary, shall be completed by one of the following options: - Wrap each fabric together at a support post with both ends fastened to the post, with a 1-foot
- Overlap silt fence by installing 3-feet passed the support post to which the new silt fence roll is attached. Attach old roll to new roll with heavy—duty plastic ties; or,
- Overlap entire width of each silt fence roll from one support post to the next support post. Attach filter fabric to the steel posts using heavy—duty plastic ties that are evenly spaced within the top 8—inches of the fabric.
- Install the silt fence perpendicular to the direction of the stormwater flow and place the silt fence the proper distance from the toe of steep slopes to provide sediment storage and access for maintenance and cleanout.
- Install Silt Fence Checks (Tie-Backs) every 50-100 feet, dependent on slope, along silt fence that is installed with slope and where concentrated flows are expected or are documented along the proposed/installed silt



FLAT-BOTTOM TRENCH DETAIL

FILTER FABRIC,

COMPACTED

EARTH

HEAVY DUTY PLASTIC TIES

18-IN. TO 24-IN.

South Carolina Department of Health and Environmental Contro

BURY FILTER FABRIC

AT LEAST 12-INCHES

S	ILT	FEN	1CE		
STANDARD DRAWING NO.	SC-(03	Page	1	of
NOT	TO	SCA	ΙF	FEBRU	JARY 20
1101		$\mathcal{I} \mathcal{I} \mathcal{I} \mathcal{I} \mathcal{I} \mathcal{I} \mathcal{I} \mathcal{I} $		Γ	ATE

- SILT FENCE POST REQUIREMENTS Silt Fence posts must be 48—inch long steel posts that meet, at a minimum,
- the following physical characteristics. — Composed of a high strength steel with a minimum yield strength of
- Include a standard "T" section with a nominal face width of 1.38—inches and a nominal "T" length of 1.48—inches.
- Weigh 1.25 pounds per foot (± 8%)
- 2. Posts shall be equipped with projections to aid in fastening of filter fabric.
- should have a minimum cross section of 17-square inches and be composed of 15 gauge steel, at a minimum. The metal soil stabilization plate should be completely buried. 4. Install posts to a minimum of 24—inches. A minimum height of 1— to 2—

3. Steel posts may need to have a metal soil stabilization plate welded near the


bottom when installed along steep slopes or installed in loose soils. The plate

- inches above the fabric shall be maintained, and a maximum height of 3 feet shall be maintained above the ground.
- 5. Post spacing shall be at a maximum of 6-feet on center.
- SILT FENCE FABRIC REQUIREMENTS
- 1. Silt fence must be composed of woven geotextile filter fabric that consists of the following requirements:
- Composed of fibers consisting of long chain synthetic polymers of at least 85% by weight of polyolefins, polyesters, or polyamides that are formed into a network such that the filaments or yarns retain dimensional stability relative to each other;
- Free of any treatment or coating which might adversely alter its physical
- properties after installation; - Free of any defects or flaws that significantly affect its physical and/or
- filtering properties; and, Have a minimum width of 36-inches.
- 2. Use only fabric appearing on SC DOT's Qualified Products Listing (QPL), Approval Sheet #34, meeting the requirements of the most current edition of the SC DOT Standard Specifications for Highway Construction.
- 3. 12-inches of the fabric should be placed within excavated trench and toed in when the trench is backfilled.
- 4. Filter Fabric shall be purchased in continuous rolls and cut to the length of the barrier to avoid joints.
- 5. Filter Fabric shall be installed at a minimum of 24-inches above the ground.

- SILT FENCE INSPECTION & MAINTENANCE
- Ihe key to functional silt fence is weekly inspections, routine maintenance, and regular sediment removal.
- 2. Regular inspections of silt fence shall be conducted once every calendar week and, as recommended, within 24-hours after each rainfall even that produces 1/2-inch or more of precipitation.
- 3. Attention to sediment accumulations along the silt fence is extremely important. Accumulated sediment should be continually monitored and removed when
- 4. Remove accumulated sediment when it reaches 1/3 the height of the silt
- 5. Removed sediment shall be placed in stockpile storage areas or spread thinly across disturbed area. Stabilize the removed sediment after it is relocated.
- Check for areas where stormwater runoff has eroded a channel beneath the silt fence, or where the fence has sagged or collapsed due to runoff overtopping the silt fence. Install checks/tie-backs and/or reinstall silt fence,
- 7. Check for tears within the silt fence, areas where silt fence has begun to decompose, and for any other circumstance that may render the silt fence ineffective. Removed damaged silt fence and reinstall new silt fence
- 8. Silt fence should be removed within 30 days after final stabilization is achieved and once it is removed, the resulting disturbed area shall be permanently

South Carolina Department of Health and Environmental Control

SILT FENCE STANDARD DRAWING NO. SC-03 PAGE 2 of 2 GENERAL NOTES FEBRUARY 201



CAROLINA


SOUTH

COUNTY,

UNION

DETAIL

STANDARD




STATE	COUNTY	ROAD/ROUTE NO.	SHEET
SC	UNION	BOAT RAMP	4F

Temporary Seeding - Upstate

Species	lbs./ac	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Browntop Millet (Alone)	40												
Browntop Millet (Mix)	10												
Rye Grain (Alone)	56												
Rye Grain (Mix)	10												
Rye Grass (Alone)	50												
Rye Grass (Mix)	8												
For Steep Slopes/Cut Slopes													
Weeping Lovegrass (Alone)	4												
Weeping Lovegrass (Mix)	2												

Permanent Seeding - Upstate

Species	Lbs/Ac	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Bahia Grass (Alone)	40									•			
Bahia Grass (Mix)	30												
Bermuda Grass (hulled) (Alone)	8-12												
Bermuda Grass (hulled) (Mix)	4-6												
Fescue, Tall (KY31) Alone	40												
Fescue, Tall (KY31) mix	20												
Sericea Lespedeza (Scarified) Alone or Mix (inoculate with EL Innoculant	40												
Ladino Clover (mix only) Innoculate with AB Innoculant	2												
		F	or St	eep S	lope	s/Cut	Slope	es					
Weeping Lovegrass (Alone)	4												
Weeping Lovegrass (Mix)	2												
Crownvetch (Mix) (Inoculate with Type M Innoculant	8-10												



UNION COUNTY, SOUTH CAROLINA

CHECKED BY:

SCALE: 30:1



